



SA PGM Operations

Kwezi Shaft – Kroondal West

HPI: IOD Investigation

Date of injury:18 June 2020

Date of presentation:14 May 2021



SAMI Entry Examination and Making Safe Day of Learning





Ensuring value creation for all stakeholders is a fundamental requirement for sustainability

Zero Harm Strategic Framework









Kwezi Shaft Injury Statistics







Details of Injured

- Full names
- Employer •
- Coy. No •
- Age
- Passport no •
- Occupation •
- Total years service
- Injury sustained
- Location
- Time of Incident •
- Residing at •

- : Katiso Elias Mosoale
- : Sibanye Stillwater
- : Z0717526
- : 47 Years
- : RC657947

:02

- : Team Leader Underground
- : 12 Years 5 Months
 - : Multiple injuries: Upper limbs & Lower Limbs
- : KWE 10LS 01 PNL008 115W
- : 12:05
 - : 16497 Sondela Village Boitekong
- Dependents •

After establishing the employee's family is in Lesotho, TEBA was contacted to convey the news. Confirmation was received on the 19th June 2020 that his wife and two daughters namely Nteboheleng Mosoale (21 yrs) and Rorisang Mosoale (14yrs) was duly informed. Due to current lockdown restrictions, TEBA could not transport his wife to Milpark as per practice, but Dr Tjale took over to update his wife on progress of Mr. Mosoale. Unit Manager-HR contact details has been shared with his wife in order to have direct contact to the shaft and or if any clarity or assistance was required.







On 18 June 2020 at approximately 12:10, it was reported that a gravity induced fall of ground (FOG) occurred at 10 South Panel 8, at up-dip 115 West.

The crew was in the process of drilling 4,5m anchor support with a bolter when a FOG, measuring 1,72m x 0,85m x 0,3m, occurred from the side of the brow that was being supported (The up dip was mined from the strong side of the fault).

A brow of 1,18m was created at a flat dipping fault (40°) during the previous blast and the brow was in the process of being supported. The drilling vibrations from the bolter loosened the side of the newly created brow which resulted in the rock, weighing approximately 1403 kg, falling from the brow face. The rock struck the Team Leader, Mr Mosoale who was standing next to the bolter's boom, on his left side. He sustained multiple fractures to his left forearm and left lower leg.

He was airlifted to Milpark Hospital in a stable condition where he was under the care of a neuro surgeon. His left forearm has been amputated on the 20th of June 2020.

Plan of Incident Scene



Note: Sketch not to scale



Photo's of Incident Scene





Photo taken from down-dip position looking up-dip towards the brow and up-dip panel face



Photo taken from down-dip position showing where the rock dislodged from the brow face



Photo taken of the FOG that struck Mr. Masoale



Photo taken of hanging wall & support immediately downdip of the 40° flat dipping fault – TARP 2 conditions



Photo taken of installed support on strong side of 40° flat dipping fault. Spaced 1m x 1,4m and better than standard

Rock Mass Management





Unsafe Acts

• Standing in the vicinity of the boom whilst lowering the TRS.

Unsafe Conditions

- Unsupported ground condition created when the boom was lowered, resulted in the rock to become loose from the brow face where the support hole was drilled, and toppled over causing the FOG injury.
- TARP 3 support instructions were issued to address the 40° flat dipping fault and brow. The faults was picked up in the adjacent boards of the up-dip where the FOG occurred.

Root causes

- Incorrect drilling and support installation sequence (the procedure at the time allowed for 1 row to be completely drilled before anchor installation took place).
- Position of people during boom operations.

System Control/Management Failure

- Unsafe support drilling and installation practice (row of six support holes drilled along the fault zone without installing support units).
- Support sequence of installation not provided / available at the time of the incident.



Basic cause	Action	Responsible person	Planned Date	Actual Date
Unsafe support drilling and installation practice (row of six support holes drilled along the fault zone and friable hanging wall without installing support units).	Revise the Procedure of installation of secondary support when drilling with a bolter.	Christo Haasbroek (Rock Engineer)	03 July 2020	03July 2020
Support layout and sequence of installation not provided.	Special Instruction – Installation of secondary support drilling with a bolter.	Lance Sapsford (Mine Manager)	22 June 2020	22 June 2020
Standing next to the boom whilst lowering the TRS. (Temporary Roof Support)	Conduct PTO'S on Support drilling with a Bolter	All Mine Overseers	22 June 2020	On Going



Similar to drilling and supporting primary support, a long anchor must be drilled and installed prior to moving to the next hole.

support holes are drilled, using an AARD / Sandvic Bolter



Step 1

Panel examined, barred and safe declaration done for entire face.

Support holes marked as per standard or TARP 3 support instructions.

Install 1 row of temp. support units at 1,5m ahead of marked row of cable anchor support holes.

Bolter operator prepare Bolter and drill steel for support hole drilling and support crew prepare material for cable anchor support installation.



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 2

Drill the 1st cable anchor support hole, starting on the **<u>Up-dip</u>** side of the panel.

When the hole limit length is reached, stop drilling and move the boom to the next support hole position and activate the TRS and stab jack against hanging wall.

Do **<u>not</u>** start drilling the next hole yet.



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 3

Support crew enters and examine and bar the hanging wall where the hole was drilled.

Stillwater

Install 1 x temp. support unit midway between the drilled support hole and next hole to be drilled, max. 0,75m from the support hole.

Install the 1st cable anchor at the 1st hole from the **<u>Up-dip</u>** side of panel and pretension the cable anchor, grout and crop the anchor (complete installation).

Support crew moves out of panel face



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 4

Once the 1st cable anchor is installed, grouted, tensioned and cropped, start drilling the 2nd cable anchor support hole.

When the hole limit length is reached, stop drilling and move the boom to the next support hole position and activate the TRS and stab jack against hanging wall.

Do **not** start drilling the next hole yet.



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 5

Support crew enters and examine and bar the hanging wall where the hole was drilled.

Install 1 x temp. support unit midway between the drilled support hole and next hole to be drilled, max. 0,75m from the support hole.

Install the 2nd cable anchor at the 2nd hole from the **<u>Up-dip</u>** side of panel and pre-tension the cable anchor, grout and crop the anchor (complete installation).

Support crew moves out of panel face



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 6

Once the 2nd cable anchor is installed, grouted, tensioned and cropped, start drilling the 3rd cable anchor support hole.

When the hole limit length is reached, stop drilling and move the boom to the next support hole position and activate the TRS and stab jack against hanging wall.

Do **<u>not</u>** start drilling the next hole yet.



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 7

Support crew enters and examine and bar the hanging wall where the hole was drilled.

Install 1 x temp. support unit midway between the drilled support hole and next hole to be drilled, max. 0,75m from the support hole.

Install the 3rd cable anchor at the 3rd hole from the **<u>Up-dip</u>** side of panel and pretension the cable anchor, grout and crop the anchor (complete installation).

Support crew moves out of panel face



support holes are drilled, using an AARD / Sandvic Bolter



Side

Step 8

Once the 3rd cable anchor is installed, grouted, tensioned and cropped, start drilling the 4th cable anchor support hole.

When the hole limit length is reached, stop drilling and move the boom to the down-dip sidewall or move bolter back and wait for complete anchor installation before moving forward to the next row of support holes to be drilled.



support holes are drilled, using an AARD / Sandvic Bolter



Step 9

Support crew enters and examine and bar the hanging wall where the hole was drilled.

Install the 4th cable anchor at the 4th hole from the **Up-dip** side of panel and pretension the cable anchor, grout and crop the anchor (complete installation).

Once the complete row anchor support is installed grouted, tensioned and cropped, remove the row of temp. support units, using a remote release sling.

Support crew moves out of panel face



support holes are drilled, using an AARD / Sandvic Bolter Stillwater Face Step 10 C/L Mark the new row of cable anchor Max \bigcirc support as per standard or TARP 3 2m Max 1m Max support instructions, with temp. support Up-dip Down-dip 1m at the face still in place. 1,5m Side Side 0 0 0 0 0 0 0 0 Max Max 0.75m 0.75m 1.5m 1.5m 1m 1m 0 0 0 0 1.5m Legend Cable anchors 0 0 0 0 Temp. support New Support 6m \bigcirc Reef Dip



Side

Procedure at 6m bords mining Norm, where each support holes are drilled, using an AARD / Sandvic Bolter Sibanye Stillwater



Step 12 Drill the 1st cable anchor support hole, starting on the **<u>up-dip</u>** side of the panel.

Down-dip When the hole limit length is reached, stop drilling and move the boom to the next support hole position and activate the TRS and stab jack against hanging wall.

Do **<u>not</u>** start drilling the next hole yet.

<u>Repeat Steps 2 – 9 for completing the row</u> of support.





Questions and comments